8th

Floor Pine

The floor to be of No. 1 tounged and groved seasoned pine at least one inch in thickness.

9th

Ceiling plastering &c

Inside to be ceiled with No. 1 seasoned pine tonged and groved ceiling from the floor up to at least 4 feet, the balance of the walls together with ceiling over head to be finished by being lathed and plastered all of good materials well prepared and put on. The plastering to be of two common coats and one finishing coat.

10th

Partition

Partition which seperates the anti room from the school room, is to have two doors, and made to open into the anti room these doors may be 4 panneds

Doors from anti room 2-8 x 6-8

2 ft 8 in and 6 ft 8 in. The anti Room may be finished with ceiling plank on its walls but to be plastered overhead the same as the school Room.

11th

Platform

Teachers Platform 6 feet long and 4 feet 9 in wide, 14 or 15 inches high with a step at each end 10 inches wide also a platform at the east end of the school room 8 feet long and 10 inches high, Also a Black board at a suitable hight above this platform, which may be 3½ feet wide.

12th

Flue

Flue to be built of good sound brick laid in good lime and sand mortar, well