

# JOB ESTIMATE

## DEPARTMENT BUILDINGS AND GROUNDS UNIVERSITY OF KANSAS

Date July 29, 1940

Department Physical Education

Description of job Floodlighting golf driving range

8 - No. 2AL45AAH3 General Electric Athletic field floodlights with mounting for 2" pipe	@ \$11.50	92.00
8 - Pcs. 2" galv. pipe, 20 ft. long for posts	@ .20 ft.	32.00
8 - Secondary racks	@ .60	4.80
3000 ft. (340 lbs.) #6 weatherproof wire	@ 19.00 per 100 lbs.	64.60
1 - No. 97313 Sq. D. safety switch, 100 ampere with 3 poles and solid neutral, 125-250 volts		<u>8.53</u>
		201.93

*Labor*

*25.00*

*226.93*

Job number.....

Cost:

Labor.....

Matl..... \$.....

Date completed.....

Total estimated cost \$ 201.93

Foreman *Raymond L. Crow*