

# JOB ESTIMATE

## DEPARTMENT BUILDINGS AND GROUNDS UNIVERSITY OF KANSAS

Date November 16, 1939

Department Physical Education

Description of job Installation of lighting for skating at field south of hill.

2000 feet #4 weatherproof wire	\$61.64
15 boiler tubes 20 feet long	-----
15 secondary racks	11.25
1 No. 97314 Sq. D. safety switch 200 amperes, 125/250 volts, 3 poles solid neutral	15.13
Electricians labor	20.00
	<u>\$108.02</u>

1-No. 8508-DXL-1 Sq. D. mechanically held contactor  
200 amperes, 250 volts, 60 cycles, 2 poles \$111.76

1-No. 9001-320-D Sq. D. push button station \$2.50

Job number.....

Cost:

Labor.....

Matl..... \$.....

Date completed.....

Total estimated cost \$.....

Foreman Raymond L. Crow