

## Reconstruction of Golf Course

No. 1 hole	Necessary improvements - filling in of ditch in front of green, possibly 20 loads of soil, and seeding on top so that all may be mowed out through the green. Level the paths in No. 1 fairway and build large 30 foot tees; sand and oil on the green once a year; removal of one tree, if possible. Estimate . . . . \$120.00
No. 2 hole	Seeding around greens and tile drainage under greens since it is built under a bank; sand and oil; removal of one tree if possible. Estimate . . . . . 60.00
No. 3 hole	Leveling of ridge between tee and green; tile drainage in the swamp and bunkers around greens; leveling of fairways and seed. Estimate . . . . . 75.00
No. 4 hole	Both trees need removing in middle of fairway; drainage tile above green just below old log cabin; sand and oil and new base construction; fairway seed. Estimate . . . . . 40.00
No. 5 hole	New fairway topping for whole distance; filling in of swamp and road across fairway; 30 loads of soil and possibly all new seeded fairway; green base of clay and oil and sand and oil top. . . . . 100.00
No. 6 hole	Good shape. Oil and sand on the green; 20 ft. tee and leveling fairway only. Estimate . . . . . 15.00
Total estimate of reconstruction of course . . . . . \$410.00	
	Rest would be labor and maintenance costs only <u>1400.00</u>
	<u>\$1810.00</u>

I sincerely believe that this six-hole golf course can be maintained in first class condition for \$1500.00 a year provided student labor is furnished by CSEP.

If 3 more holes are added the maintenance should not be more than \$200.00 a year after they are built. Building three extra holes would be optional and require some moving of trees and extra labor.

It is my belief that this course could be supervised by expert hands and kept in first class condition with the above approved budget.

Sincerely,

Glenn Oatman  
Golf Coach.