

2.

reconstruction

No 1 hole necessary improvement

- filling in of ditch in front
of green possible 20 loads of soil
and seeding on top so that all
may be mowed out through the green.
Leveling the paths in no 1 fairway and
building large 30 ft trees - sand and
oil on the green over a year - (removal
of one tree if possible)
estimate \$120.00

No 2. hole

Seeding around greens and tile
drainage under green since it
is built under a bank - sand
and oil - removal of one tree if
possible estimate - \$68.00

No 3 hole.

Leveling of ridge between 2nd and
green - tile drainage in the
swamp and bunkers around greens
and leveling of fairways and
seed estimate \$75.00